

KOLAR DIVISION.

Notice.

The attention of the public is invited to the advertisement in the *Mysore Gazette*, dated 9th May 1918, pages 416 and 417, Part IV, calling for tenders for "extending the District Office building at Kolar to provide accommodation to the District Economic Superintendent at Kolar."

V. V. KARVE,
Offg. Executive Engineer.

TUMKUR DIVISION.

Dated 3rd May 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 29th May 1918, for constructing Offices for the District Committee and District Economic Superintendent Tumkur District, Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 12 noon and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (500) five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Offices for the District Committee and District Economic Superintendent at Tumkur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing offices of District Committee and the District Economic Superintendent in Tumkur.

Items of work	Per	Quantity
Earthwork excavation and filling basement	C. yd.	96
Burnt stone in chunam	C. ft.	3,971
Burnt brick in chunam	"	5,796
Burnt brick archwork	"	63
Burnt stone slabs roughly dressed	S. ft.	744
Burnt stone slabs nicely dressed	"	475
Cutting grooves to stone pillars	Each	14
Chunam plastering	Sq.	111'90
Chunam pointing	"	5'78
White and color washing	"	117'68
Teakwood work wrought and put up with wood oiling	C. ft.	241'3
Roofing with 1st class Mangalore tile on teak reapers, etc., complete...	Sq.	42'00
Ridge tiles set in mortar	R. ft.	176
Binding wall over roof	"	156
Zinc sheet for the valleys	S. ft.	152
Teak planking 94" do	"	152
Roofing with pucoa terrace	Sq.	2'15
Cornice 9" thick	R. ft.	16
Ornamental parapet wall over terraced roof as per plan	Lump sum	
Teakwood panelled doors with iron clamps, etc., complete	S. ft.	392
Teak windows outside panelled and inside glazed with iron bars, clamps, etc.	"	347
Teak ventilators with glazed shutters, etc.	"	156
Circular ventilator	"	14
Chocolate painting silicate	Sq.	20'00
Teakwood sun shades	Each	14
Teakwood eave boards with wood oiling	R. ft.	503
Teak finials	Each	7
Flooring with Cuddappa slabs over 3" concrete bed and cement pointing	Sq.	17'60
Teak pendants	Each	22
Flooring with Mangalore tiles over 3" concrete bed and cement pointing	Sq.	7'04
Clearing site and levelling ground	Lump sum	

N. G. KRISHNA IYENGAR.

Offg. Executive Engineer.